9. The quotations should be noted in figures as well as in words .—

Items of work	Per	Quantity	Rate	Cost
I Bund—				
Earthwork	C.yd.	2374		
Turfing the slopes	Sqr.	239		
Revetment	C.yd.	528		
Resetting the old stone revetment	,,	472		
Gravel backing	,,	497		
Grade stones	Each	18		
Index stones	,,	18		
Registered No. and date stones	,,	1		
B. M. stones	,,	2		
Jungle clearing of bund	Grade	17		
Total ...	...	...		
II Sluice—				
Earthwork	C.yd.	115		
Concrete in surki mortar	C.ft.	64		
Burnt brick in surki mortar	,,	426		
Plastering with surki mortar	Sqr.	2·20		
Burnt stone slabs 6″ thick	S.ft.	97		
Providing a new plug with lock and key arrangements.	Each	1		
Cast iron pipe 6″	R.ft.	27		
Total ...	...	...		
III Weir—				
Earthwork	C.yd.	45		
Concrete in surki mortar	C.ft.	112		
Burnt brick in surki mortar	,,	213		
Plastering with surki mortar	Sqr.	1		
Burnt stone slabs 6″ thick	S.ft.	156		
Rough stone work	C.yd.	27		
Total ...	...	...	...	...
Contingencies ..	...	...	...	...
Grand Total ...	...	...	...	...

S. SRINIVASA IYER,
Executive Engineer.

SHIMOGA DIVISION.

Dated 20th September 1927.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 15th October 1927, for constructing Barr Sepoys' Huts at Shimoga. An approximate estimate of quantity for the unit is given below. These quantities are not guaranteed. The work should be completed by the end of May 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed:—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Barr Sepoy's Huts at Shimoga," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Shimoga Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate (modified) for constructing two Barr Sepoys' Huts at Shimoga.

No.	Items of work	Per	Quantity
1	Earthwork excavation and filling in	C.yd.	71
2	Concrete stone jelly in mortar	C.ft.	799
3	Burnt stone in clay including bond stones	"	1,367
4	Burnt brick in clay do	"	1,607
5	Brick in chunam arch work	"	25
6	Brick in chunam top of walls and soffits of doors, etc. ...	"	347
7	Burnt stone slabs one line dressed 6" thick	S.ft.	130
8	Honne wood work wrought and put up	C.ft.	59·65
9	Mud plastering	Squares	59·26
10	Chunam plastering	"	29·82
11	Pointing with chunam	"	4·06
12	White washing 2 coats	"	19·26
13	Colour washing do	"	29·82
14	Flooring with 3" jelly concrete and plastering with chunam mortar mixed with cement rendering.	"	6·96
15	Gravelling the compound	C.yd.	2
16	Coping with brick in chunam and plastering over ...	R.ft.	146
17	Honnewood battened doors with ½" diameter, iron bars with painting.	Sq.ft.	75
18	Honne wood battened doors complete including painting ...	"	154
19	Honne wood wall shelves with cross planks, complete ...	"	23
20	Cement concrete drain 6" dia.	R.ft.	48
21	Constructing seats in latrines, lumpsum	..	...
22	Roofing with First Class Mangalore tiles on teak reepers, rails, etc., complete.	Squares	11·27
23	Ridge tiles set in mortar	R.ft.	42
24	Terrace brick on edge	Squares	56
25	Cornice 5"	R.ft.	22
26	Parapet wall as per design	"	21
27	Chunam boarders	"	48
28	Ventilating tiles (smoke tiles)	Each	6
29	Tarring, lumpsum	...	...
30	Clearing site do	...	...
31	Mortar and pestle do	...	...

Dated 20th September 1927.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 30th September 1927, for constructing Barr Sepoys' Quarters at Honnali, Shimoga District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. and 5 P.M., on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 500 (five hundred only) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Barr Sepoys' Quarters at Honnali, Shimoga District," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Shimoga Circle, Shimoga, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of the cost of constructing Barr Sepoys' Quarters at Honnali, Shimoga District. (Block 2 huts).

No.	Items of work	Per	Quantity
1	Clearing site, levelling ground, etc.	L. S.	...
2	Earthwork excavation and filling in basement	C.yd.	47
3	Burnt stone in clay foundation and basement	C.ft.	1,682
4	Burnt brick in clay superstructure	,,	1,952
5	Do do mortar	,,	356
6	Burnt stone slabs dressed	S.ft.	179
7	Honne wood battended doors with fixing clamps, etc. ..	,,	147
8	Honne wood battended windows with iron bars and fittings, etc., complete.	,,	52
9	Honnewood work wrought and put up, complete ...	C.ft.	48·25
10	Roofing with First Class Mangalore tiles, teak reepers and fixing eave tiles, etc.	Sqr.	10·34
11	Ridge tiles set in mortar and cement pointing	R.ft.	27
12	Providing ventilating tiles	No.	4
13	Burnt brick in mortar coping with chunam plastering ...	R.ft.	86
14	Plastering with mud	Sqr.	17·18
15	Do with chunam	,,	25·04
16	White and colour washing	,,	42·22
17	Chunam pointing basement	,,	2·63
18	Silicate painting	,,	4·24
19	Wood oiling and tarring wood work	,,	5·00
20	Providing mortar and pestle stone	No.	2
21	Concrete flooring with fine plastering	Sqr.	6·67
22	Chunam borders over roof	R.ft.	70
23	Providing concrete drains inside and outside	,,	64
24	Providing ovens and constructing seats in latrine, etc. ..	L. S.	...
25	Plain cornice at gable-ends	R.ft.	70

M. A. SRINIVASACHARI,
Executive Engineer.